

**BID SHEET
FOR
NELSON SPORTS COMPLEX PAVEMENT IMPROVEMENTS #046
ROLLING MEADOWS PARK DISTRICT
ROLLING MEADOWS, IL
PHASE 2 South Lot
Dated: February 1, 2017**

NELSON SPORTS COMPLEX PAVEMENT IMPROVEMENTS					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	Fine Grading (See Note 1)	6580	SY		
2	Excavation and Remove Excess Material for proposed sidewalk	85	CY		
3	Inlet Filter Basket	5	EA		
4	Tree Protection Fence	410	LF		
5	Concrete Washout Facility	1	EA		
6	1 1/2" HMA Surface Course, Mix D, N50	6250	SY		
7	2 1/2" HMA Binder Course, IL-19.0, N50	6250	SY		
8	2" HMA Surface Course, Mix D, N50	130	SY		
9	Detectable Warning	110	SF		
10	5" Portland Cement Concrete Sidewalk	3584	SF		
11	4" Compacted Aggregate Base Course (under proposed sidewalk)	340	SY		
12	Concrete Curb and Gutter	830	LF		
13	24" Diameter Inlet	1	EA		
14	15" Storm Sewer, RCP Class I	5	LF		
15	Connect to Existing Storm Sewer	1	EA		
16	Adjust Existing Manhole Rim	3	EA		
17	4" Solid Yellow Paint	4100	LF		
18	24" Solid Yellow Paint	60	LF		
19	Handicap Parking Symbols	3	EA		
20	Parking/Handicap Parking Signage (salvage & relocate)	3	EA		
21	Wheel Stops	12	EA		
22	Sawcut Existing HMA Pavement	100	LF		
23	Remove Existing Bituminous Pavement	6700	SY		
24	Sawcut Existing Concrete Sidewalk, Curb and Gutter	45	LF		
25	Remove Existing Concrete Sidewalk	705	SF		
26	Remove Existing Curb and Gutter	670	LF		
27	Remove Existing Catch Basin	1	EA		
28	Undercut Existing Aggregate Base and Replace with Compacted Aggregate (See Note 3)	550	CY		
29	Permit Fees (Allowance)	1	LS	\$15,000.00	\$15,000.00
30					
31					

BID SHEET
FOR
NELSON SPORTS COMPLEX PAVEMENT IMPROVEMENTS #046
ROLLING MEADOWS PARK DISTRICT
ROLLING MEADOWS, IL
PHASE 2 South Lot
Dated: February 1, 2017

NELSON SPORTS COMPLEX PAVEMENT IMPROVEMENTS					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
32					
BIDDERS PROPOSAL FOR BASE BID:					

(FIGURES)

(WORDS)

General Notes:

- 1 Fine grading price shall include cutting and filling existing aggregate base course to meet grades provided for HMA pavement, curb and gutter, concrete sidewalk, and HMA bike path.
- 2 Undercutting shall include removal of existing stone base and replacement with compacted aggregate IDOT CA-6. Undercut material shall be hauled to 3900 Owl Drive and stockpiled. Quantity calculated as 25% of subgrade approximately 1' thick.
- 3 This bid proposal assumes restoration and seeding will be performed by the Park District.